BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Remodelling of Secondary drain on 3rd cross Bhadrappa layout in ward No. 8, Kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	17.35	Dismantling of flexible pavements and disposal of dismantled materials and stacking serviceable and unserviceable materials separately - Manual Means - Bituminous Course	Cum	1063.70	Rupees One Thousand Sixty Three and Seventy Paise Only
2	88.71	Dismantling of flexible pavements and disposalof dismantled materials and stacking serviceable and unserviceable materials separately - Manual Means - Granular course	Cum	750.20	Rupees Seven Hundred Fifty and Twenty Paise Only
3	397.37	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work	Cum	204.60	Rupees Two Hundred Four and Sixty Paise Only
4	62.43	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead I By Manual Means B Cement Concrete Grade M-15 & M-20	Cum	2038.30	Rupees Two Thousand Thirty Eight and Thirty Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	30.45	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6518.60	Rupees Six Thousand Five Hundred Eighteen and Sixty Paise Only
6	54.81	Providing Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6172.10	Rupees Six Thousand One Hundred Seventy Two and Ten Paise Only
7	27.00	Removing and Resetting of Footpath Slab / Removing and refixing 225mm thick slabs	Sqm	235.00	Rupees Two Hundred Thirty Five Only
8	277.50	Providing and fixing pre cast covering slab 250mm thick made out of RCC 1:2:4 and jelly 20mm down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc., complete as directed by the Engineer in charge of the work.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
9	2.57	Removing and refixing slabs	Sqm	235.00	Rupees Two Hundred Thirty Five Only
10	0.28	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete.	Sqm	1922.00	Rupees One Thousand Nine Hundred Twenty Two Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
11	14.00	Providing, laying, spreading and compacting graded stone aggregate to Wet Mix Macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2633.40	Rupees Two Thousand Six Hundred Thirty Three and Forty Paise Only
12	60.90	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface	Sqm	476.30	Rupees Four Hundred Seventy Six and Thirty Paise Only
13	7018.35	Providing and fixing steel work in built up tabular (round, square, rectangular hollow tubes etc.,) trussses etc., including cutting, hoisting, fixing in position and applying priming coat of approved primer coat, including welding and bolted with special shaped washer set etc., complete. Electric resistance, conduction butt welded tubes including cost of materials, labour usage, charges of machinery as per specifications and as per direction of Engineer in charge of the work.	kg	121.00	Rupees One Hundred Twenty One Only
14	565.86	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3)	Cum	81.40	Rupees Eighty One and Forty Paise Only
15	724.30	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	t.Km	115.50	Rupees One Hundred Fifteen and Fifty Paise Only

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
Byatarayanapura Division
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
BBMP, Bangalore - 92
ಬೃ.ಬ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))